PALACE DIVISION.

ADVERTISEMENT.

The 14th November 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Palace Division, up to 21st November 1887, for constructing Siladar Lines at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A. M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing Siladar Lines at Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed Abstract Estimate for constructing Siladar Lines at Bangalore.

Items of Work.	Per.	Quantity.
Earthwork, excavation	C. Yd.	27
Stone in clay, foundation and basement	C. Ft.	844
Burnt brick in clay	do	1,705
Plastering with mud	Sq.	12·15
Pointing with chunam	„	1,006
Honne wood work..	C. Ft.	17·38
Stone slabs	Sq. Ft.	65
Color washing	Sq.	13·80
Whitewashing	„	12·85
Drains	R. Ft.	14
Earthwork	C. Yd.	19
Gravelling	do	19
Roofing with 2nd Class Mangalore tiles and Honne wood reepers ..	Sq.	6·20
Honne wood door 3 × 6	No.	2
Do 2½ × 5	„	2
End wall inclusive of painting, &c.	L. S.	..
The above details are for one hut 30 in No. in all are to be constructed.		

R. T. SCALDWELL,
Executive Engineer.

KOLAR DIVISION.

ADVERTISEMENT.

The 10th November 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 5th December 1887, for extending the Urigam Gold Field Railway Feeder to

474

Kamasamudram. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1889.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. —— in cash or Government promissory notes, as earnest money, and be superscribed "Tender for extending the Urigam Gold Field Railway Feeder to Kamasamudram," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of Work.		Approximate Quantity.	Rate per C. Yd.
Earthwork, ordinary soil	C. Yds. .	32,710	
Do rocky soil.. . ..	do ..	21,443	
Turfing	L. S. ..	..	
Clearing jungle	Furlongs..	41	
Blasting rock	L. S. ..	..	
Removing boulders	do ..	..	
Rough stone revetment	C. Yds..	200	
Forming the road	Furlongs..	52	
Rough metal..	C. Yds..	2,000	
Mile stones	No..	7	
Furlong stones	No..	52	
Sign post	No..	1	
Collection of metal	C. Yds..	5,720	
Carting metal, 2 miles lead..	do ..	1,980	
Do 1 do	do ..	880	
Do ½ do	do ..	440	
Do ¼ do	do ..	2,420	
Collection of gravel	do ..	4,449	
Carting gravel, 2 miles lead	do ..	1,539	
Do 1 do	do ..	684	
Do ½ do	do ..	342	
Do ¼ do	do ..	1,197	
Consolidation of metal	do ..	5,720	
Do gravel	do ..	4,449	

Tunnels.

21 of 1 vent 3 × 3 ..
1 of 1 vent 3 × 5 ..
1 of 1 vent 3 × 6 ..
1 of 1 vent 4 × 6 ..
1 of 2 vents 5 × 5 ..
1 of 10 vents 5 × 5 ..

Total No. 25.

Culverts.

Y. SRINIVASA RAO,
Executive Engineer.

TUMKUR DIVISION.

ADVERTISEMENTS.

The 25th October 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 30th November 1887, for restoring the Gurgadahalli Tank, Registered No. 70, Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 1 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money, and be superscribed "Tender for restoring the Gurgadahalli Tank;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate Bill.

Detailed abstract estimate of restoring Gurgadahalli Tank, Registered No. 70, Tiptur Taluk.

Items of Work.	Per	Quantity.	Rate.	Cost.
Bund.				
Earthwork	C. Yd.	19,769		
New stone work	do	2,432		
Old stone work	do	953		
Grade stones	..	42		
B. M. Stones	..	2		
Total....				
Sluices.				
No. I Sluice—Cutting and clearing .	L. S.	30		
No. II Sluice—Earthwork .. .	C. Yd.	400		
Brick in chunam	C. Ft.	591		
Concrete	do	173		
Plastering	Sq.	2·78		
Covering slabs	S. Ft.	117		
Front and orifice stones .. .	L. S.	3		
Gibbet stones	do	15		
Total....				
Waste Weirs.				
Excavation	C. Yd.	3,706		
Brick in chunam	C. Ft.	2,151		
Plastering	Sq.	5·76		
Covering slabs	S. Ft.	291		
New stone work	C. Yd.	487		
Total....				

476

The 28th October 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 20th November 1887, for restoring the Ponnasandra Tank, Registered No. 276, Pavagada Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur between the hours of 1 to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring the Ponnasandra Tank;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of the probable cost of restoring Ponnasandra Tank, Registered No. 276, Pavagada Taluk.

Items of Work.	Per	Quantity.	Rate.	Cost.
Bund.				
Earthwork	C. Yd.	27,245		
Old stone work	do	2,976		
New stone work	do	3,358		
Grade stones	Each.	52		
B. M. Stones	do	2		
Sluice No. I.				
Repairs	L. S.	40		
Sluice No. II.				
Dismantling and removing old sluice ..	L. S.	15		
Brick in surki mortar	C. Ft.	679		
Plastering	Sq.	5·00		
Slab stones	L. S.	15		
Left Waste Weir.				
Cutting and clearing lower and upper approaches.	L. S.	150		
Right Waste Weir.				
Excavation	C. Yd.	160		
Brick in chunam	C. Ft.	1,774		
Plastering	Sq.	6·00		
Slab stones	S. Ft.	113		
Old stone work	C Yd.	152		
New stone work	do	208		

C. T. DALAL,
Executive Engineer.

CHITALDROOG DIVISION.

ADVERTISEMENT.

The 8th November 1887.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 5th December 1887, for restoring the Anaji Tank, Registered No. 44 of Davangere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1888.

Bund.			
Earthwork	13,736	Cubic yards.	
Old stone work	4,474	Do	
New stone work	790	Do	
Gravelling	624	Do	
Grade stones	31	Stones.	
B. M. Stones	2	Do	
Tank No. stone	1	Stone.	
Right Kodi.			
Brick in chunam	2,916	Cubic feet.	
Slab stones	1,656	Square feet.	
Rough stone work to apron	248	Cubic yards.	
Sluices.			
Constructing cisterns	2	Cisterns.	

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldroog between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given above, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government promissory notes as earnest money and be superscribed "Tender for restoring the Anaji Tank, R. No. 44," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of any tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. RANGA RAO,
Offg. Executive Engineer.

VACCINE DEPARTMENT.

The 9th November 1887.

The Deputy Inspector of Vaccination, Hassan District, will move towards the following Hobbles of the Hassan Taluk from or during the third and fourth weeks of the current month or till his other movements are notified thereof:—

1. Salgame
2. Hassan Kasaba
3. Bilahalli.
4. Ponnathpur.
5. Alur.

for the purpose of inspecting the work of the Vaccinators and he with his staff (consisting of 2 vaccinators) will vaccinate those willing to undergo the vaccine operation. Letters, &c. should be addressed to Hassan.

S. VENKATACHAR,
Dy. Inspector of Vaccination, Hassan Distt.